



SOUTHFIELD • DETROIT

400 Galleria Officentre
Suite 555
Southfield, Michigan 48034
phone 248.352.8310
fax 248.352.1821
www.neumannsmith.com

BULLETIN #4

DATE	August 09, 2018
PROJECT NAME	Saint Kenneth Catholic Church Worship Space Addition & Renovation
PROJECT NUMBER	2014166
DISTRIBUTION	Via Email

- A. This form is being issued after contract award and includes drawings, sketches, text and other information used to solicit a proposal for a change in the work. This bulletin, or portions thereof, become part of the contract documents only after being incorporated in a formal change order.
- B. The following documents are issued for and become part of this Bulletin:
 - Drawings: T-1, S-1, S-2, C-1, C-2, C-3, C-4, C-5, C-6, C-7, C-8, C-9, C-10, C-11, C-12, C-13, C-14, C-15, C-16, C-17, C-18, C-19, S-1, S-2, GDS, W-1, W-2, W-S, LP-1, LP-2. All drawings listed were issued as part of the construction set dated 07.25.2018.
 - Sketches: NA
 - Specifications: NA
- C. No other documents have been revised or are being reissued for this Bulletin. Refer to the existing documents, previous revisions (if any) and the following text of descriptions of the modified work. Contact the Architect if further clarification or information is required.
- D. The titles following each item are for reference only. The work entailed may affect trades other than those referenced in the title. Quote all required work.
- E. Provide an itemized breakdown for each item and sub-item of work. Include labor and material costs.

CIVIL DRAWINGS

Item No. 1 – Civil Documents

Refer to Drawings:

- A. Refer to Civil write up for scope of work.

End of Bulletin #4



Greg L. Ash, P.L.S.
8495 North Territorial
Plymouth, MI 48170

[734] 416-9650
Fax: [734] 416-9657
www.glasurveyor.com

August 9, 2018

Ms. Alexis Polsinelli
Neumann Smith Architecture
400 Galleria Officentre
Suite 555
Southfield, MI 48034

RE: St Kenneth Church Bulletin #4

Dear Ms. Polsinelli:

Per your request the following is a write up detailing changes in the civil design based on previous design plans vs approved plans.

- The previous design called for a single run of 190 feet of 96" aluminized steel pipe. The approved plan now calls for a dual run of 130 feet of 72" aluminized steel pipe.
- The previous design utilized a pump station to convey storm water to the existing on site storm system. The pump station has been eliminated in the approved plans.
- The previous design tied the storm water from the new detention to an existing catch basin within the parking lot area. The design now as approved will discharge the storm water via gravity to an existing structure within the Sly Drain easement adjacent to the West property line of the church property.
- The Wayne County outlet control structure has been relocated approximately 80 feet to the North of its previous location.
- Pretreatment units 31 and 32 were moved to the East, outside of the Sly Drain easement.
- Existing MH 23 within the parking lot was moved approximately 40 feet to the East.
- Proposed Hydrant 1 was moved approximately 25 feet to the North.
- Storm water profiles were updated to reflect the revised storm water design.
- A detail for proposed structure 29 (Drywell) was added to the plans.
- The North radius of the inbound lane for the entrance to the church has been revised to meet the Wayne County entrance requirements.

- Storm structure 30 was added to the approved plans.
- Approximately 80 feet of 12" C-76-CL IV pipe and 275 feet of 6" PVC Schedule 80 pipe were added to the approved plans.
- Wayne County details RS-1 and D-6 were added to the approved plans
- Changes to some notes and details have been revised within the approved plans.

If you have any questions, please feel free to contact our office.

Sincerely,



Scott A. Schumacher
Director of Engineering