

Queen of the Holy Rosary Wea Master Plan

February 04, 2024

Agenda

- 1. Introductions
- 2. Project Background
- Master Plan
 - + Site Plan
 - + Floor Plans
 - + Images: Bird's Eye View & Interior View
- 4. Cost Review
- 5. Questions

Introductions



Team Introduction

Queen of the Holy Rosary

- Building Committee
- Finance Council
- Parish Council

SFS Architecture

- Marsha Hoffman
- Kelly Stindt
- Derek McMurray
- Consultants
 - Bob D. Campbell & Co.
 - PKMR Engineers
 - MKEC Engineers
 - CMR (Construction Management Resources, LLC)

Project Background



Project Background

Our Process So Far

ASSESSMENTS

- April 2022 Historic Church Assessment completed
- December 2022 Campus Structures Assessment completed
- Assessed Church, School, Residence, Chapel, Rectory, Daycare, Parking, Cemetery, and other structures
- · Reports available on the QHR website

MASTER PLANNING


- December 2023 Master Plan completed
- Programming Phase
 - Staff and parishioner interviews
 - Space Needs Program
- · Campus Planning
 - New church and daycare location options
- New Church Design Concept
- Cost Estimate
- Report available on the QHR website













The gutters and downspouts on the east and north additions overhang the wall in a traditional method.

A portion of the roof was recently replaced. It was determined the roof still has 5-7 years of life, so the Parish

Masonry and Mortar Join


The structure has a decorative design of 2 shades of red brick on all elevations. The brick is in good condition. The morter is buff and in good condition as well.

chose to repair areas where leaks occur around penetrations and other areas of concern

Under the trailers to the north, there are veneer masonry units replicating 8x16 CMU. The veneer is failing at the corners and missing in some areas. Around 40% of the mortar joints are cracked. The veneer was not tooled properly leaving excess mortar on the block veneers.









Master Plan



SITE PLAN

Parking Spaces:

- 187 Existing spaces
- **100** *New* spaces (Phase 3)
- 287 Total spaces

Building Additions

- Phase 1: Middle School
- · Phase 2: Daycare

New Buildings

Phase 3: New Church



SITE PLAN

PHASE 1: Middle School


- 4 middle school classrooms
- 1 STREAM classroom
- Support spaces

PHASE 2: Daycare

- 1 Infant room 3-4 infants
- 1 One y.o. room 4 kids
- 1 Two y.o. room 5-6 kids

Total: 12-14 kids

- Indoor Playroom
- Director Office
- · Laundry / Kitchen / Support
- Storm shelter
- Outdoor Playground




Master Plan

PHASE 3 FLOOR PLAN

Level 01 - Ground

- Fully Accessible
- Gathering Space
- 24/7 Adoration Chapel
- Baptismal Font
- Nave with Seating for:
 - 730 People (tight)
 - 575 People (comfy)
- Full Choir
- Vesting and Working Sacristies
- · Ample Storage




Master Plan

PHASE 3 FLOOR PLAN

Level 00 - Basement

- · Fully Accessible
- Youth Room
- Meeting Room
- Parish Offices
- Additional Restrooms
- Future:
 - Parish Hall and support spaces



Concept Images Bird's Eye




Concept Images

Interior Nave



Master Plan Implementation Sequence



Cost Estimate

Cost Estimate

Conceptual Costs Per Phase

Building Project:

- Phase 1 Middle School Classrooms \$2.7 million*
- Phase 2 Daycare \$1.7 million*
- Phase 3 New Church \$26 million*

Spring Feasibility Study

Summer Capital Campaign

PHASE Middle School Phase 1 6,500sf EXISTING CEMETERY

New drive and

drop-off lane

PHASE 2 Daycare

NEW SANITARY FIELD

*Total project cost



Project Cost vs. Construction Cost

Construction Cost

- + Soft Costs
- = PROJECT COST

Soft Costs include:

- Professional Fees
- Civil Engineering & Landscape Design
- Geotechnical Testing
- Permitting
- Special Inspections
- A/V Systems
- Fixtures, Furniture, and Equipment
- Artwork and Pews
- · Etc.

PHASE 3: NEW CHURCH

Construction Cost	\$22,551,390*
New Church	\$22,551,390
Design Contingency (17.5%)	(Included above)

Soft Costs	\$3,403,167
Fees, FFE, etc.	\$2,501,112
Const. Contingency (4%)	\$902,055

TOTAL PROJECT COST \$25,954,557

^{*} Includes escalation to midpoint of construction: March 2026

Next Steps

- Spring Feasibility Study
- 2. Summer Capital Campaign

